



BUILDING ALTERATION WORKS NOTES (All studwork walls)

ROOM G3
 Room G3 opened up with the removal of existing counter and screen.
 Shelves between G3 and G5 removed to link rooms together.
 Door and partition in corridor outside G3 to be removed. 2ND door from G3 to corridor to be removed and gap filled with studwork.

ROOM G5
 Remove entrance door and partition wall including ceiling.

ROOM G6
 Take ductwork serving G8 through the wall at high level terminating with a grill next to the door.
 Replace the existing manual wall vent at low level in the opposite corner of the room with larger manual vent.

ROOMS G8 & G9
 Modify existing extract and supply ductwork and provide new ductwork for supply only air to these rooms. New grills to be positioned as shown.
 Install new Centrifugal Supply fan and associated controls within corridor position outside G9/Server Room .Also include a heater to warm the air where required from the Courtyard. Design equipment and ductwork for 3 A/Cs per hour .

SERVER ROOM
 New wall mounted axial fan – 9” version to reduce noise and extract at the rate of 70 litres/sec.

New supply only fan

Bideford Town Hall – New Business Hub
Building Alteration Works
 Drawing No. BIDBUSHUB-1004 Drawn MRB
 Dated Nov 2018

